Greybeard Fence LLC
375 Duck Dr
Mars Hill, NC 28754 US
grant@greybeardfence.com
www.greybeardfence.com

Estimate

ADDRESS
Joshua Henderson
304 Black Mountian Ave.
Black Mountain, NC 28711

ESTIMATE # 5601
DATE 12/03/2024

SALESPERSON
Grant Rehder

JOB
Veterans Park Baseball Fields

DATE	PRODUCT	QTY	RATE	AMOUNT
	Commercial Chain Link Fencing FIELD 1 BACKSTOP: Install approximately 120 linear feet of 30' tall galvanized chain link fencing. 4" SS40 posts set in concrete 72" below grade on 8' centers. 1-5/8" SS40 rails on 6' centers with an additional rail 3' above grade for additional strength. 7 rails in total. Bottom 6' of chain link mesh is 6 gauge. Next 24' of chain link is 9 gauge.	1	33,210.00	33,210.00
	Commercial Chain Link Fencing FIELD 1 FOUL LINES: Install approximately 248 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing. 2.5" SS40 terminal posts set in concrete 36" below grade. 2" SS40 line posts set in concrete 36" below grade on 10' centers (max). 1-5/8" top rail and 7 gauge bottom tension wire. Includes (2) 4' wide walk gates with lockable fork latches.	1	8,437.00	8,437.00
	Commercial Chain Link Fencing FIELD 1 OUTFIELD: Install approximately 350 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing. 2.5" SS40 terminal posts set in concrete 36" below grade. 2" SS40 line posts set in concrete 36" below grade on 10' centers (max). 1-5/8" top rail and 7 gauge bottom tension wire. Includes (1) 12' wide double swing gate with a lockable industrial drop rod. Polymer safety top cap on all top rail of outfield fencing.	1	14,647.00	14,647.00
	Commercial Chain Link Fencing FIELD 2 BACKSTOP: Install approximately 120 linear feet of 30'	1	33,210.00	33,210.00

DATE	PRODUCT	QTY	RATE	AMOUNT
	tall galvanized chain link fencing. 4" SS40 posts set in concrete 72" below grade on 8’ centers. 1-5/8" SS40 rails on 6’ centers with an additional rail 3’ above grade for additional strength. 7 rails in total. Bottom 6’ of chain link mesh is 6 gauge. Next 24’ of chain link is 9 gauge.			
	Commercial Chain Link Fencing FIELD 2 FOUL LINES: Install approximately 248 linear feet of 6’ tall, 2" x 9 gauge galvanized chain link fencing. 2.5" SS40 terminal posts set in concrete 36" below grade. 2" SS40 line posts set in concrete 36" below grade on 10’ centers (max). 1-5/8" top rail and 7 gauge bottom tension wire. Includes (2) 4’ wide walk gates with lockable fork latches.	1	8,437.00	8,437.00
	Commercial Chain Link Fencing FIELD 2 OUTFIELD: Install approximately 350 linear feet of 6’ tall, 2" x 9 gauge galvanized chain link fencing. 2.5" SS40 terminal posts set in concrete 36" below grade. 2" SS40 line posts set in concrete 36" below grade on 10’ centers (max). 1-5/8" top rail and 7 gauge bottom tension wire. Includes (1) 12’ wide double swing gate with a lockable industrial drop rod. Polymer safety top cap on all top rail of outfield fencing.	1	14,647.00	14,647.00
	Commercial Chain Link Fencing FIELD 3 BACKSTOP: Install approximately 120 linear feet of 30’ tall galvanized chain link fencing. 4" SS40 posts set in concrete 72" below grade on 8’ centers. 1-5/8" SS40 rails on 6’ centers with an additional rail 3’ above grade for additional strength. 7 rails in total. Bottom 6’ of chain link mesh is 6 gauge. Next 24’ of chain link is 9 gauge.	1	33,210.00	33,210.00
	Commercial Chain Link Fencing FIELD 3 FOUL LINES: Install approximately 248 linear feet of 6’ tall, 2" x 9 gauge galvanized chain link fencing. 2.5" SS40 terminal posts set in concrete 36" below grade. 2" SS40 line posts set in concrete 36" below grade on 10’ centers (max). 1-5/8" top rail and 7 gauge bottom tension wire. Includes (2) 4’ wide walk gates with lockable fork latches.	1	8,437.00	8,437.00
	Commercial Chain Link Fencing FIELD 3 OUTFIELD: Install approximately 350 linear feet of 6’ tall, 2" x 9 gauge galvanized chain link fencing. 2.5" SS40 terminal posts set in concrete 36" below grade. 2" SS40 line posts set in concrete 36" below grade on 10’ centers (max).	1	14,647.00	14,647.00

DATE	PRODUCT	QTY	RATE	AMOUNT
	1-5/8" top rail and 7 gauge bottom tension wire. Includes (1) 12’ wide double swing gate with a lockable industrial drop rod. Polymer safety top cap on all top rail of outfield fencing.			
	Commercial Chain Link Fencing FIELD 4 BACKSTOP: Install approximately 120 linear feet of 30’ tall galvanized chain link fencing. 4" SS40 posts set in concrete 72" below grade on 8’ centers. 1-5/8" SS40 rails on 6’ centers with an additional rail 3’ above grade for additional strength. 7 rails in total. Bottom 6’ of chain link mesh is 6 gauge. Next 24’ of chain link is 9 gauge.	1	33,210.00	33,210.00
	Commercial Chain Link Fencing FIELD 4 FOUL LINES: Install approximately 178 linear feet of 6’ tall, 2" x 9 gauge galvanized chain link fencing. 2.5" SS40 terminal posts set in concrete 36" below grade. 2" SS40 line posts set in concrete 36" below grade on 10’ centers (max). 1-5/8" top rail and 7 gauge bottom tension wire. Includes (2) 4’ wide walk gates with lockable fork latches.	1	6,056.00	6,056.00
	Commercial Chain Link Fencing FIELD 4 OUTFIELD: Install approximately 305 linear feet of 6’ tall, 2" x 9 gauge galvanized chain link fencing. 2.5" SS40 terminal posts set in concrete 36" below grade. 2" SS40 line posts set in concrete 36" below grade on 10’ centers (max). 1-5/8" top rail and 7 gauge bottom tension wire. Includes (1) 12’ wide double swing gate with a lockable industrial drop rod. Polymer safety top cap on all top rail of outfield fencing.	1	12,764.00	12,764.00

Please mail payments to:
Greybeard Fence Solutions
375 Duck Dr.
Mars Hill, NC 28754

TOTAL **$220,912.00**

Greybeard Fence Solutions does accept credit card payments, with a 3% processing fee.

Thank you!

Accepted By

Accepted Date

All private utilities, known or unknown are not the responsibility of Greybeard Fence, LLC