G & S Fence Company
(Grindstaff and Sons)
759 Graphite Road
Old Fort, NC 28762
828-668-4647
gandsfenceco@gmail.com
williamsjl11@yahoo.com

QUOTE
January 13, 2025

Town of Black Mountain
304 Black Mountain Avenue
Black Mountain, NC 28711
Attn: Josh Henderson

Job Location: Veterans Park Baseball Fields, Black Mountain, NC

Base on the specifications furnished to us. The quote is as follows:

Field and Backstop # 1	**$43,050.00**
Field and Backstop # 2	**$43,050.00**
Field and Backstop # 3	**$43,050.00**
Field and Backstop # 4	**$39,525.00**
	$168,675.00

2 Year Workmanship Warranty
15 Year Limited Manufacture Warranty

Outlook

Fencing Specs For Veterans Park Baseball Fields

From Joshua Henderson <joshua.henderson@tobm.org>
Date Fri 12/13/2024 1:04 PM
To williamsjl11@yahoo.com <williamsjl11@yahoo.com>

Great talking to you this morning. Below are the specs for the fencing that we are seeking a quote for. Please let me know if you have any questions or need additional information. Thank you!

FIELD 1 BACKSTOP: Install approximately 120 linear feet of 30' tall galvanized chain link fencing.
4" SS40 posts set in concrete 72" below grade on 8' centers.
1-5/8" SS40 rails on 6' centers with an additional rail 3' above grade for additional strength. 7 rails in total.
Bottom 6' of chain link mesh is 6 gauge. Next 24' of chain link is 9 gauge.

FIELD 1 FOUL LINES: Install approximately 248 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing.
2.5" SS40 terminal posts set in concrete 36" below grade.
2" SS40 line posts set in concrete 36" below grade on 10' centers (max).
1-5/8" top rail and 7 gauge bottom tension wire.
Includes (2) 4' wide walk gates with lockable fork latches.

FIELD 1 OUTFIELD: Install approximately 350 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing.
2.5" SS40 terminal posts set in concrete 36" below grade.
2" SS40 line posts set in concrete 36" below grade on 10' centers (max).
1-5/8" top rail and 7 gauge bottom tension wire.
Includes (1) 12' wide double swing gate with a lockable industrial drop rod.
Polymer safety top cap on all top rail of outfield fencing.

FIELD 2 BACKSTOP: Install approximately 120 linear feet of 30'
tall galvanized chain link fencing.
4" SS40 posts set in concrete 72" below grade on 8' centers.
1-5/8" SS40 rails on 6' centers with an additional rail 3' above grade for additional strength. 7 rails in total.
Bottom 6' of chain link mesh is 6 gauge. Next 24' of chain link is 9 gauge.

FIELD 2 FOUL LINES: Install approximately 248 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing.
2.5" SS40 terminal posts set in concrete 36" below grade.
2" SS40 line posts set in concrete 36" below grade on 10' centers (max).
1-5/8" top rail and 7 gauge bottom tension wire.
Includes (2) 4' wide walk gates with lockable fork latches.

FIELD 2 OUTFIELD: Install approximately 350 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing.
2.5" SS40 terminal posts set in concrete 36" below grade.
2" SS40 line posts set in concrete 36" below grade on 10' centers (max).
1-5/8" top rail and 7 gauge bottom tension wire.
Includes (1) 12' wide double swing gate with a lockable industrial drop rod.
Polymer safety top cap on all top rail of outfield fencing.

FIELD 3 BACKSTOP: Install approximately 120 linear feet of 30' tall galvanized chain link fencing.

4" SS40 posts set in concrete 72" below grade on 8' centers.
1-5/8" SS40 rails on 6' centers with an additional rail 3' above grade for additional strength. 7 rails in total.
Bottom 6' of chain link mesh is 6 gauge. Next 24' of chain link is 9 gauge.

FIELD 3 FOUL LINES: Install approximately 248 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing.
2.5" SS40 terminal posts set in concrete 36" below grade.
2" SS40 line posts set in concrete 36" below grade on 10' centers (max).
1-5/8" top rail and 7 gauge bottom tension wire.
Includes (2) 4' wide walk gates with lockable fork latches.

FIELD 3 OUTFIELD: Install approximately 350 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing.
2.5" SS40 terminal posts set in concrete 36" below grade.
2" SS40 line posts set in concrete 36" below grade on 10' centers (max).
1-5/8" top rail and 7 gauge bottom tension wire.
Includes (1) 12' wide double swing gate with a lockable industrial drop rod.
Polymer safety top cap on all top rail of outfield fencing.

FIELD 4 BACKSTOP: Install approximately 120 linear feet of 30' tall galvanized chain link fencing.
4" SS40 posts set in concrete 72" below grade on 8' centers.
1-5/8" SS40 rails on 6' centers with an additional rail 3' above grade for additional strength. 7 rails in total.
Bottom 6' of chain link mesh is 6 gauge. Next 24' of chain link is 9 gauge.

FIELD 4 FOUL LINES: Install approximately 178 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing.
2.5" SS40 terminal posts set in concrete 36" below grade.
2" SS40 line posts set in concrete 36" below grade on 10' centers (max).
1-5/8" top rail and 7 gauge bottom tension wire.
Includes (2) 4' wide walk gates with lockable fork latches.

FIELD 4 OUTFIELD: Install approximately 305 linear feet of 6' tall, 2" x 9 gauge galvanized chain link fencing.
2.5" SS40 terminal posts set in concrete 36" below grade.
2" SS40 line posts set in concrete 36" below grade on 10' centers (max).
1-5/8" top rail and 7 gauge bottom tension wire.
Includes (1) 12' wide double swing gate with a lockable industrial drop rod.
Polymer safety top cap on all top rail of outfield fencing.

Black Mountain
Recreation & Parks

Josh Henderson, CPRP, CPO
Recreation & Parks Director
Town of Black Mountain
304 Black Mountain Ave
Office: 828.419.7205
Cell: 828.767.0064