HUNTLEY CONSTRUCTION

121 CHARLOTTE HWY, ASHEVILLE, NC 28803
828-298-1686 828-298-1685
Email: huntleyconst@bellsouth.net
N.C. LICENSE #5264
UNCLASSIFIED - UNLIMITED

June 30, 2026

Town of Fletcher
300 Old Cane Creek Road
Fletcher, NC 28732

RE: Town Park Trail Bank Stabilization

==========

Huntley Construction Company Proposes To Furnished Equipment, Materials and Labor To Do The Following Scope of Work:

Removal of existing wooden rail fence - removal of any vegetation hanging over bank failure including removal off site - reshaping of failed bank if needed - installation of matting at failed area - stabilization of area with rock boulders at toe of slope failure - according to McGill Associates Boulder Toe Protection drawing - seeding and matting of reworked slope - re-installing wood fence - repair of existing Walking Trail disturbed during re-construction of bank failure – seeding and matting all other disturbed areas.

This price is based on repairing approximately Forty Feet of Bank.

For The Sum Of **$ 59,736.00**