SAFE INDUSTRIES

KME Change Order

Customer Name	**LincolntonFFD**
Address	
Change Order #	**CO#1**
Date	**12.12.2025**
GSO #	**11854**

In some cases the items contained within alter your original purchase specification and/or price. Please carefully review this list and return a signed copy of this letter by the date listed below. Delays beyond this timeframe may alter KME's ability to deliver your apparatus to contract requirements, may necessitate price increases to the options, or limit our ability to provide some or all of the changes.

Change Item #	Add/Delete/ Clarification	Part #	Item Description	Ext Cost/ Credit Per Truck	Select or Write In Yes or No
1			Add a Diamond Plate locker compartment to the forward section of the pumphouse one (1) each side.		
2			The added locker compartments will be painted with Black Line-x material.		
3			A vertical pull-out tool board will be provided inside the officer side locker compartment on the pumphouse.		
4			All ground ladders will be changed to Duo Safety brand.		
5			One 35' 2-section ladder will be removed and replaced with a 28' 2-Section ladder		
6			A 15-amp duplex household receptacle will be provided in the upper portion of the L5 on the rear wall. The outlet will be wired to the shoreline.		
7			A 15-amp duplex household receptacle will be provided in the upper portion of the R5 on the rear wall. The outlet will be wired to the shoreline		
8			The R3 body compartment will be changed to Split depth as far as needed to allow for 400 feet of 4 inch to be stored inside the hosebed. The split will be roughly 12 inches in.		
9			The bolt on aerial egress will be painted Red FBCH 995842.		
10			The aerial ladder will be painted Black FBCH 9000.		
11			The cab will be painted two-tone Black FBCH 9000 over Red FBCH 995842.		
12			The body will be painted single tone Red FBCH 995842.		
13			The aerial sign panels will be painted Black FBCH 9000 to match the aerial device		

14			The cab interior door striping will be changed to Red Diamond Grade and Black Scotch-lite material.		
15			The aerial outrigger striping will be changed to Red Diamond Grade and Black Scotch-lite material		
16			The rear of body striping will be changed to Red Diamond Grade and Black Scotch-lite material.		
17			There shall be aerial creeper controls provided at the tip of the aerial.		
18			The SCBA brackets in the cab seats will be changed to the new Bostrom Secure-all series.		
19			The Officer side rear oil dry hopper will be removed and replaced with a triple cylinder storage module.		
20			The multiplex pump shift will be moved to the right of the Class One Multiplex screen on the driver side lower wing panel.		
21			The tank to pump valve control will be flipped so in the pulled out position the valve is closed and with the pushed in location opens the valve		
22			The air horn on the officer side will be controlled by a foot switch located on the officer side lower wing panel, the lanyard control will be deleted		
23			The Federal Q2B activation on the officer side will be controlled by a foot switch located on the officer side lower wing panel.		
24			A Federal Q2B brake switch will be relocated in the officer side lower dash switch pack.		
25			The aluminum treadplate overlay on the cab roof will be painted with Black Line-x.		
26			The aluminum treadplate overlays and battery access doors on the cab will be painted with Black Line-x.		
27			The Cast Product cab steps will be painted with Black Line-x		
28			The cab auxiliary steps and mounting brackets will be painted with Black Line-x.		
29			The exterior cab door paddle latches will be provided Black in color.		
30			The cab exterior door window trim extrusion will be provided Black in color		
31			The cab door windowsill protectors will be deleted.		
32			The cab door frame and jamb trim will be deleted.		
33			The Hansen cab grab handles will be provided with a Black anodized finish.		
34			The cab front and side grills will be painted Black.		
35			The aluminum treadplate overlay on the rear cab wall will be painted with Black Line-x.		
36			The cab fenderettes will be painted with Black Line-x.		
37			The Retrac cab mirrors will be provided with a black housing.		
38			The front and rear rims will be changed to Dura-Black finish with Black lug and hub trim covers.		
39			The Sig 4 fuel pocket door will be painted Black.		

40			The M6 turn signals will be provided with a Black bezel.		
41			The headlight buckets will be painted Black		
42			The Hi Viz brow light will be provided Black in color.		
43			All Whelen warning lights on the cab and body will be provided with Black Bezels		
44			All DOT Marker and turn lights will be provided with a Black Bezel.		
45			The Tecniq license plate light will be provided with a Black Bezel.		
46			The Tecniq body step lights will be provided with a Black Bezel.		
47			The Whelen M6 Quad stack DOT mounting bezel will be painted Black.		
48			The Whelen aerial access ladder illumination lights will be ordered with Black mounting flanges.		
49			The Grover air horns will be ordered Black in color		
50			The electric siren speaker covers will be painted Black.		
51			The Federal Q2b siren will be ordered in Black Chrome.		
52			The On Scene Solutions slide out step cover will be painted with Black Line-x.		
53			The running boards will be painted with Black Line-x.		
54			The officer’s floating hosewell exterior surface will be painted with Black Line-x		
55			The driver and officer side full width light shield/step will be painted with Black Line-x.		
56			The treadplate overlays on the top and front of the body will be painted with Black Line-x.		
57			The turntable access ladders and the treadplate panels will be painted with Black Line-x.		
58			The body c-channel rub rails will be painted with Black Line-x.		
59			The body fenderettes will be painted with Black Line-x.		
60			The body and pumphouse Hansen handrails will be provided in Black anodized material.		
61			The front of body Innovative Controls folding steps will be provided Black in color.		
62			The outrigger cover panels will be changed to Black Line-x painted steel versions.		
63			The storage box for the rescue rope pulley system will be painted with Black Line-x		
64			The Tecniq lights on the heel pin step cover will be provided with a Black Bezel.		
65			The Hi Viz lights at the tip of the ladder will be provided Black in color		
66			The fluid used for the transmission will be TES-668 synthetic.		

67			The cab will be painted using the same process and standards as all cabs painted at the REV build facility, using PPG products and approved processes. This will not affect any warranties or warranty terms called out in the specifications. The paint will adhere to the REV Fire Group Paint Appearance Standards RFG-SR-01 including all finish sanding and buffing.		
68			The underside of the cab will be coated with a black rubberized automotive undercoating.		
69			All fittings, fasteners, and hoses/lines shall be substituted as needed by the REV build facility to complete the build. These substitutions shall not affect the overall form, fit, function of the truck overall, but may have some aesthetic difference. The items include, but are not limited to, air lines, fuel lines, heater hoses, frame hardware, brake lines, and interior or exterior fasteners.		
70			All chassis air hoses will be reinforced with Synflex hose with reusable fittings. All air hoses will be protected with heat resistant split loom.		
71			All cab seat risers and EMS compartments will be welded into the cab structure.		
72			Scotch-lite lettering with a drop shadow will be provided on the front bumper.		
73			Gold Leaf lettering with a drop shadow will be provided on the front cab doors.		
74			Gold Leaf lettering with a drop shadow will be provided on the rear cab doors.		
75			Scotch-Lite lettering without a drop shadow will be provided on the cab side panel.		
76			Scotch-Lite lettering without a drop shadow will be provided on the body side panel		
77			Two (2) Scotch-Lite Fire Department patches will be provided on the aerial sign panel.		
78			The NY roof hook on left side of the aerial will be mounted on the top of the fly section like GSO 11368.		
79			An 8’ rubbish hook will be provided and mounted on the right side of aerial on the top of the fly section like GSO 11368.		
80			The stainless-steel protectors on the body will be deleted.		
81			The body roll up door curtains will be painted Job Color Red. The body top gutter and door frames will be painted Job Color Black.		
82			The Cast product step in the aerial fly section will be painted with Black Line-x material		
83			A storage compartment will be provided in the driver side center tandem for the storage of the Two (2) Zico wheel chocks.		
84			A aluminum tread plate saw box with a recessed handle will be provided on the turntable deck. The box will be painted with Black Line-x.		
85			Nut-serts will be provided for all body access panels and attachment as much as possible		

86			24" Painted Steel Front Bumper Extension Treadplate Gravel Shield Treadplate Gravel Shield Standard Installation Gravel Shield to be Finished with Black Bedliner One (1) Hose Well at Center of Bumper Extension One (1) Hinged Latched, Treadplate Cover on Center Well - Thumb Latch Center Well - General Storage Center Well - Black Bedliner One (1) Hose Well on the Officer Side of Bumper Extension One (1) Hinged Latched, Treadplate Cover on Officer's Side Well - D-Ring Officer Well General Storage Officer's Side Well - Black Bedliner Two (2) Tow Eyes Tow Hooks/Eyes Below Bumper Tow Hooks/Eyes Painted Front Bumper Chevron Striping		
				Total for Changes	**$0.00**

Authorized Signature of the Purchaser _____

Printed Name _____

Title _____

Date _____

Add	Yes
Delete	No
Clarification	