Rader Construction
License No. 78228
828-384-4272 or 828-384-4272
raderr43@gmail.com
300 Clara Valley Rd
Brevard NC. 28712

Proposal: Roof

French Broad Community Center:

Cliff Justus

Building & Grounds Supervisor

Description:

Replace existing flat roofing material.

Currently there is a granulated roll roofing material covering the section of low pitch roof that is on the front of the building.

Water damage that is noticeable on front vinyl siding is due to the fact that the roofing material/application is faulty.

To provide a warranty approximately 6 square of roofing will need to be replaced with a modified bitumen roofing material.

Rotten decking will be replaced with new decking.

To enable a proper tie/in to the architectural shingles the three lower rows of shingles will be removed to allow for transition material to be installed. After modified roofing is installed on low pitch new closely matching architectural shingles will be installed to complete the job.

Total: $6,350.00 includes all labor and materials

Robert Rader Construction.

THANK YOU FOR YOUR BUSINESS!