ESTIMATE

Bortz Landscaping Services, LLC
dba InDemand Landscape Systems
PO Box 1517
Black Mountain, NC 28711

info@indemandlandscaping.com
+1 (828) 669-5478
www.indemandlandscaping.com

Bill to
Black Mountain Montessori School
101 Carver Ave
Black Mountain, NC 28711

Estimate details
Estimate no.: 1213
Estimate date: 04/03/2025

#	Date	Product or service	Description	Qty	Rate	Amount
1.		**LABOR**	Labor by hour to create drainage around school to mitigate the flooding due to damage from Hurricane Helene. Locate, deliver and install approximately 330 feet of 10" ABS double wall pipe to create drainage. Locate, deliver and install approximately 125 feet of 4" smooth wall SDR 35 smooth wall pipe. Locate, deliver and install approximately 5 tons of pea gravel to bed pipe. Excavate soil for pipe installation. Connect downspouts to main pipe. Backfill, compact material. Seed and straw new drainage area. Cleanup at completion.	1	$6,500.00	$6,500.00
2.		**MATERIALS**	Application of Materials: 10" ABS double wall pipe (approx 330 feet)	1	$9,460.00	$9,460.00
3.		**MATERIALS**	Application of Materials: 4" smooth wall SDR 35 smooth wall pipe (approx 125 feet)	1	$2,250.00	$2,250.00
4.		**Pea Gravel**	Application of Pea Gravel (price per ton) (approx 5 tons)	1	$475.00	$475.00
5.		**Mini-Ex**	Equipment usage Mini Excavator	1	$6,500.00	$6,500.00
6.		**Landscapers Choice Grass Seed**	Landscapers choice grass seed	1	$540.00	$540.00

7.	**WHEAT STRAW**	Application of Wheat straw used on bare lawns after seeding.	1	$225.00	$225.00

Total **$25,950.00**

Note to customer

Thank you for the opportunity to present this proposal.

Accepted date **Accepted by**